IMPACT AMALYSIS OF THE CAMPACT SHIPPING CONTAINER(U)
SOUTHWEST RESEARCH INST SAN ANTOMIO TX
D J POMERENING ET AL JUL 85 SMRI-86-8461-882
F/G 13/4 171 AD-A189 829 UNCLASSIFIED NL



MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A



## OTTC\_EILE CORY

3 823

## IMPACT ANALYSIS OF THE CAMPACT SHIPPING CONTAINER

AD-A189 8

0

.J.

by
D. J. Pomerening
P. A. Cox



FINAL REPORT SwRI Project No. 06-8461-002

July 1985

**DISTRIBUTION UNLIMITED / APPROVED FOR PUBLIC RELEASE** 

Prepared for

U.S. ARMY TOXIC AND HAZARDOUS MATERIALS AGENCY ABERDEEN PROVING GROUND, MARYLAND 21010-5401

## **DISCLAIMER**

The findings in this report are not to be construed as an official Department of the Army position unless so designated by other authorizing documents.

UNCLASSIFIED SECURITY CLASSIFICATION OF THIS PAGE						
	REPORT DOCU	MENTATION	PAGE			
14 REPORT SECURITY CLASSIFICATION		1b. RESTRICTIVE	MARKINGS			
Unclassified		None				
2a SECURITY CLASSIFICATION AUTHORITY		3 DISTRIBUTION / AVAILABILITY OF REPORT				
NA CONTRACTOR OF THE CONTRACTO	0.00	Distribution Unlimited/Approved for Public Release				
2b DECLASSIFICATION / DOWNGRADING SCH	DULE					
NA 4 PERFORMING ORGANIZATION REPORT NUMBER(S)		5. MONITORING ORGANIZATION REPORT NUMBER(S)				
06-8461-002		A1447				
00-0401-002		AMXTH-CD-TR-86056				
6a NAME OF PERFORMING ORGANIZATION 6b OFFICE SYMBOL		7a. NAME OF MONITORING ORGANIZATION				
Southwest Research Institute	(If applicable)	U.S. Army Toxic and Hazardous Materials Agency				
Southwest Research Thistitute						
6c. ADDRESS (City, State, and ZIP Code)		7b. ADDRESS (City, State, and ZIP Code)				
P. 0. Drawer 28510		Aberdeen Proving Ground, MD				
6220 Culebra Road		21010-5401				
San Antonio, Texas 78284		<del> </del>				<del></del>
Ba. NAME OF FUNDING/SPONSORING	8b. OFFICE SYMBOL	9. PROCUREMENT INSTRUMENT IDENTIFICATION NUMBER				
ORGANIZATION H&R Technical Associates, Inc	(If applicable)					
	·	10 00 1000 00	51.41.5141.5141.41	2505		
8c. ADDRESS (City, State, and ZIP Code)		10. SOURCE OF		TASK		WORK UNIT
P. O. Box 215		PROGRAM ELEMENT NO.	PROJECT NO.	NO.		ACCESSION NO.
Oak Ridge, Tennessee 37831						İ
11 TITLE (Include Security Classification)		<u>.l</u>	<del></del>			<u> </u>
•	DACT Chinning Com	***				
Impact Analysis of the CAM	PACI Shipping con	ta iner				
12 PERSONAL AUTHOR(S)	<del></del>					
Pomerening, D. J.; Cox, P. A	•					
13a, TYPE OF REPORT 13b, TIME COVERED		14. DATE OF REPORT (Year, Month, Day) 15. PAGE COUNT				
Final FROM_	то	85,0		·	88	8 ^
16 SUPPLEMENTARY NOTATION				-		
		<del> </del>				

17. COSATI CODES

18. SUBJECT TERMS (Continue on reverse if necessary and identify by block number)

FIELD GROUP SUB-GROUP

M55 Transportation Accident, Impact Response, CAMPACT

19 ABSTRACT (Continue on reverse if necessary and identify by block number)

Nonlinear impact analyses were performed on the CAMPACT shipping container. Longitudinal and lateral drops onto rigid surfaces were treated. Analyses were performed with the ADINA computer code, and included both geometric and material nonlinearities. Modeling of the CAMPACT emphasized the inner door and door attachments in an attempt to predict the onset of leakage at the inner door seal. The CAMPACT was loaded with pallets of M55 rockets and the floor roller assembly. The contents were treated as concentrated masses applied to the inner frame at appropriate locations for each impact direction.

The traile at appropriate rocations for each impact direction.

20 DISTRIBUTION/AVAILABILITY OF ABSTRACT	21. ABSTRACT SECURITY CLASSIFICA	TION
UNCLASSIFIED/UNLIMITED 🛱 SAME AS RPT. 🔲 DTIC USERS		
22a NAME OF RESPONSIBLE INDIVIDUAL	22b TELEPHONE (Include Area Code)	22c. OFFICE SYMBOL
CPT Kevin J. Flamm	(301) 671-2424	AMXTH-CD-L

DD FORM 1473, 84 MAR

15

02

83 APR edition may be used until exhausted
All other editions are obsolete

SECURITY CLASSIFICATION OF THIS PAGE

# SOUTHWEST RESEARCH INSTITUTE Post Office Drawer 28510, 6220 Culebra Road San Antonio, Texas 78284

# IMPACT ANALYSIS OF THE CAMPACT SHIPPING CONTAINER


by
D. J. Pomerening
P. A. Cox

FINAL REPORT SwRI Project No. 06-8461-002

for

H&R Technical Associates, Inc. Oak Ridge, Tennessee

July 1985



Approved:

Clax B. Wenzel

PTIC

Alex B. Wenzel, Director Department of Energetic Systems

## **ACKNOWLEDGEMENTS**

The authors greatly acknowledge the assistance provided to them by Mr. Everton McKenzie, who generated many of the finite element models used in the CAMPACT analyses; Ms. Deborah Stowitts, who edited the report; Mrs. Rosemary Rivas, who typed the draft report; and to Mrs. Sue White, who typed the final report.

## TABLE OF CONTENTS

			Page
	ACK	NOWLEDGEMENTS	i
I.	INT	RODUCTION	1
	В.	Background Objective Scope of Work Method of Approach	1 1 1 4
II.	CAMI	PACT ANALYSIS	6
	A. B.	<ol> <li>Requirements</li> <li>Properties</li> <li>Preliminary Analyses</li> <li>Mass</li> <li>Foam Crushing - Static</li> <li>Foam Crushing - Dynamic</li> <li>Buckling</li> </ol>	6 6 14 17 17 18 18
	D.	<ul><li>5. Static Crushing Strength</li><li>Longitudinal Impact</li><li>1. Model Development</li><li>a. Finite Element Grid</li><li>b. Concentrated Masses</li></ul>	21 21 21 21 29
	Ε.	<ol> <li>Impact and Boundary Conditions</li> <li>Solution Results</li> <li>Estimate of Impact Crush Strength         Lateral Impact         Model Development         a. Finite Element Grid     </li> </ol>	30 30 35 36 36 36
	F.	<ul> <li>b. Concentrated Masses</li> <li>2. Impact and Boundary Conditions</li> <li>3. Solution Results <ul> <li>a. Static Results</li> <li>b. Dynamic Results</li> </ul> </li> <li>4. Estimate of Impact Crush Strength</li> <li>Summary of Results</li> <li>1. Longitudinal Impact</li> <li>2. Lateral Impact</li> </ul>	45 46 49 49 58 69 70 70
III	•	ESTIMATES OF M55 ROCKET FAILURE INSIDE THE CAMPACT	71
	Α.	Longitudinal Imp:ct	71
IV.	CON	CLUSIONS AND RECOMMENDATIONS	72
	A. B.	Conclusions Recommendations	72 72
٧.	REFE	ERENCES	74

## LIST OF TABLES

Table No	<u>. Page</u>	
1	Summary of Nonlinear Material Properties	16
2	Estimated Weight CAMPACT ComponentsTruck Version	17
3	Preliminary Dynamic Foam Crushing Results	20
4	Elements and Nodes for the Longitudinal Model	29
5	Flements and Nodes for the Lateral Model	45

#### I. INTRODUCTION

## A. Background

This work was performed for H&R Technical Associates in support of their evaluations of the CAMPACT shipping container (Figure 1) for the M55 rocket pallets (Figure 2). Only evaluations of the CAMPACT container are reported here; a companion structural analysis of the M55 pallet is reported under separate cover [1].

### B. Objective

The objective of this analysis was to evaluate the CAMPACT container for impact loading from 30 ft. high free fall drops onto a rigid surface. The analysis utilized the finite element method and focused on the ability of the CAMPACT to maintain a seal between the inner door and the inner frame during and following the impact. Finite element models were created for the CAMPACT which were as realistic as practical, yet conservative. The results should be appropriate for the alternative analysis in which they will be used.

#### C. Scope of Work

Two drops were analyzed, a longitudinal drop and a lateral drop. For the longitudinal drop, impact was on the door end; for the lateral drop, impact was on the side of the container. It was assumed that all points on the impacting surface struck the rigid surface at the same time. Vertical, edge and corner drops were not addressed.

Two versions of the CAMPACT shipping container are under development, a truck version and a rail version. The truck version is in a more advanced design stage; thus, the analyses performed were for the truck version only. Even for this version detailed structural drawings could not be obtained. All dimensions, materials, structural components, and attachment details were obtained from Reference 2 and from conversations with design personnel [3].

Loading of the M55 pallets within the CAMPACT was provided by H&R Technical Associates. The truck version can transport a maximum of eight (8) pallets. This was the only loading configuration considered. Fewer pallets would result in higher pallet accelerations; however, eight pallets produce the worst case loading for the CAMPACT itself. The pallets and other internal




Figure 1. CAMPACT - Truck Version [Ref. 2]




Figure 2. Pallet of M55 Missiles (in Launch Tubes) - [Ref. 2]

equipment, such as the floor roller assembly and blocking, were treated as rigid masses for the impact calculations. Details are provided in Section II.

#### D. Method of Approach

Impact of the CAMPACT on an unyielding surface can produce yielding and large deformations in the structural members. To accommodate these responses, models of the CAMPACT, which included both material and geometric nonlinearities, were formulated and solved using the ADINA computer program [4]. Two separate models were constructed, one for longitudinal impact and one for lateral or side impact. Both models included details of the inner door, inner frame adjacent to the door and connections between the inner door and the inner frame.

Because nonlinear analyses are costly to perform, steps were taken to reduce the size of the models as much as possible. For the longitudinal model, the CAMPACT was assumed to be symmetrical about both a vertical longitudinal plane and horizontal longitudinal plane, which is very nearly true. By modeling only one of these symmetrical pieces (%th of the total structure), the size of the model was reduced substantially. The model was reduced further by using concentrated masses to represent the upper end of the CAMPACT, aft of the first bay of the inner frame, and by ignoring the outer frame and foam aft of the door. The size of the lateral model was reduced by a similar process. In this case a half model was developed, with symmetry about a vertical lateral plane at the midpoint of the inner frame. As with the longitudinal model, the outer frame was ignored. Details for both models are given in Section II.

In the truck version, eight (8) pallets are placed in the container: two abreast, two high and two deep. The long axes of the pallets are aligned with the long axis of the CAMPACT. This arrangement requires blocking to fill the empty spaces between the sides of container and the pallets. No space was assumed to exist between the pallets themselves which left 12 inches to be blocked between the pallets and the side walls and 62.5 inches to be blocked between the pallets and the container ends. This blocking was assumed to be equal on each side and each end, which centered the pallets on the floor of the CAMPACT. The pallets were assumed to rest on the floor, which required that 30.5 inches of blocking be placed above the pallets. In all analyses, it was assumed that the blocking was rigid and distributed the loading from the

pallets evenly to the inside surfaces of the CAMPACT. In addition, the pallets inside the CAMPACT were assumed to act as rigid masses during the impact, i.e., their motions, whether elastic or elastic-plastic, were not coupled to the CAMPACT response.

To describe the impact of the CAMPACT on the rigid surface, all parts of the model, except the boundary which struck the rigid surface, were given an initial velocity corresponding to a free fall drop of 30 ft. The striking boundary was fixed against motion. No other forces were applied and gravity was ignored during the impact. These initial conditions adequately describe the impact event.

Results obtained were in the form of deformed shapes, permanent plastic deformation of the members, and stresses in the elements. Interpretation of the results was complex because of the three-dimensional response of the CAMPACT. The analyses were also complicated by the geometry in the region of the inner door seal. Approximations made in the model development had to be considered during interpretation of the computed results.

#### II. CAMPACT ANALYSIS

## A. Geometry

Overall geometry of the CAMPACT was shown in Figure 1, and Figure 3 gives an exploded view. The exploded view identifies the major components of the CAMPACT container. Further identification of CAMPACT components are given in Figures 4 and 5. In Figures 3 through 5 it is easy to see that the inner and outer frame assemblies are isolated from each other by a layer of structural foam. This foam is the major energy absorbing component of the system for the impact conditions being considered in these analyses.

Additional details of the CAMPACT are given in Figures 6 through 9. The truck version of the CAMPACT has an overall size of 301" x 96" x 108.5" (length x width x height) with an inside cavity of 230" x 74" x 86" (Figure 6). Figures 7, 8 and 9 show details of the door and the inner frame adjacent to the door. Special care was given to the modeling of this region of the structure because leakage of the seal was taken as the primary failure mode of the CAMPACT. Of course, any source of leakage would cause failure, but it was considered unlikely that distortions and strains would be sufficient to cause leakage in other parts of the structure. It was also assumed that the blocking offered no potential to damage the liner.

#### B. Material Properties

#### 1. Requirements

Definition of the material properties for the CAMPACT system were based on the requirements of the computer programs used to generate and analyze the system. For the two models under consideration, two programs were utilized in the analysis sequence. GIFTS [5] was utilized to generate the model, while ADINA [4] was utilized to preform the nonlinear dynamic analysis. These two programs require a slightly different definition of the nonlinear material properties. The requirements for the two systems are:

 $\underline{\text{GIFTS}}$ --For this program, the characteristics are defined in terms of the stress-strain pairs for the particular element/material combination under question.

<u>ADINA</u>—For this program, the characteristic: required are dependent on the element type and the nonlinear model being used. For the majority of elements and materials, this required the definition of the elastic modulus,




Figure 3. Outer protective structure of the shipping container. [Ref. 2]




Figure 4. Component identification: overall [Ref. 2]




Figure 5. Component identification: closure end [Ref 2]





Figure 6. Configuration control layout [Ref. 2]



0

C

(

C

•

<u>AND THE PROPERTY OF THE PROPE</u>

Containment system (for clarity, outer frame, door, and structural foam are omitted) [Ref. 2] Figure 7.




Figure 8. Detail of closure area [Ref. 2]




Figure 9. Detail of inner door seal and hinge [Ref. 2]

the yield stress, and the hardening modulus after yielding. The major exception was the foam, which was idealized as a tri-linear system. For this case, it was necessary to define the elastic modulus, the yield stress and the stress-strain pairs for the linear segments after yielding.

In all cases, these material characteristics were idealized as linear stress-strain relationships. All except the foam were considered to be bilinear. Figure 10 gives a description of the majority of the materials used in the CAMPACT. For the models developed, definition of properties for the Type 304 Stainless Steel, the A320 Grade L7C steel bolts, and the polyurethane structural foam were required. Data on the material characteristics for the three were derived from References 2, 6, 7 and 8.

#### 2. Properties

Table 1 gives material properties which were used for both the longitudinal and lateral models. For the analysis, it was sometimes necessary to adjust the values in Table 1 to take into account the geometry of the various elements under consideration. ADINA does not allow for hollow sections such as the 3 x 3 members of the inner frame. In ADINA, it was necessary to define the hollow sections as solid cross sections. To insure the proper bending stiffness or axial stiffnesses, it was necessary to modify both the geometry of the section and the material characteristics of the particular element. It was not possible to match all requirements, such as bending stiffness about both axes and the axial stiffness too. Depending on the type of element in question and its primary mode of response, the appropriate modifications were made. Specific modifications will be discussed in the appropriate sections of this report.

Another consideration is the fact that the values for the various material parameters were based on the static characteristics of the materials. For metals this approach is valid. The foam will display some change in response depending on the rate of loading [9]. Since the load rate was not known prior to the analysis it was not possible to define the actual material properties to account for strain rate effects.

Figure 10. Material identification: closure end [Ref. 2]

Copy available to DTIC does permit fully legible reproduction

Table 1. Summary of Nonlinear Material Properties

## Type 304 Stainless Steel

 $28.5 \times 10^6 \text{ psi}$ Elastic Modulus 0.26 Poission's Ratio 30,000 psi Yield Strength 113,000 psi Hardening Modulus Density 0.290 lb/in<sup>3</sup>

30,000 psi Stress No. 1 0.00105 in/in Strain No. 1 75,000 psi Stress No. 2 0.40 in/in Strain No. 2

## A320 Grade L7C Steel Bolts

 $30 \times 10^{6} \text{ psi}$ Elastic Modulus 0.30 Poisson's Ratio 105,000 psi Yield Strength 40,000 psi Hardening Modulus 0.286 lb/in<sup>3</sup> Density Stress No. 1 105,000 psi

0.0035 in/in Strain No. 1 Stress No. 2 125,000 psi 0.5 in/in Strain No. 2

## Structural Foam

Elastic Modulus 3500 psi Poisson's Ratio 0.30 140.0 psi Yield Strength 0.52 in/in Plastic Limit 900 psi Hardening Modulus

Density 0.00347 lb/in<sup>3</sup>

Stress No. 1 140.0 psi Strain No. 1 0.04 in/in 150.0 psi Stress No. 2 0.52 in/in Strain No. 2 Stress No. 3 970.0 psi 0.67 in/in Strain No. 3

The material properties defined were appropriate for this design phase analysis. Properties were chosen to give comparative results for use in alternative analysis procedures.

## C. Preliminary Analyses

### 1. Mass

The first task was to determine the mass/weight characteristics of the truck version of the CAMPACT. From the limited drawings of the system, estimates of the weights of the various components of the system were made. Table 2 gives a summary of the major components and their corresponding weight. The total weight of the system was estimated to be 40,153 lb. These calculations neglect the weights of such components as the hinges, vents, bolts, etc. Their weight was assumed to be insignificant.

Table 2. Estimated Weight CAMPACT Components--Truck Version

ELEMENTS	DESCRIPTION	WEIGHT (1b)		
Outer Skin Type 30	1 SS	501		
Outer Frame Type 304 3 x 3 x 0.125 Squa		3016		
Puncture Panel Kevlar-	29 and Type 301 SS	9738		
Structural Foam Po	olyurethane	4315		
Inner Frame Type 204 3 x 3 x 0.25 Square		4345		
Inner Door Type 304 SS 1403 4 x 6 x 0.25 Square Tubing Aluminum Honeycomb Panel with Type 304 SS Faces				
Inner Liner Type 30	4 SS	4335		
Roller Floor 1200				
Pallets Eight @ 1350	lbs each	10800		
Blocking Wood <u>500</u>				
TOTAL 40153				

## 2. Foam Crushing - Static

As a part of the analysis procedure, some static runs were made to verify the stiffness of the models elements, the mass of the system and to give an indication of system response. For these cases, an acceleration of 1g was applied to the models, and a preliminary analysis was preformed to estimate the deflection of the system. For the longitudinal model, the total deflection was estimated to be 0.0227 inches. This calculation was made using the formula:

$$\delta = P1/AE$$

where P =the load (lb)

L = the length of the foam elements (in)

A = the area of the foam elements  $(in^2)$ 

E = the Elastic Modulus (psi)

For the lateral model two static cases were considered. Since the model could respond in both the lateral (X) and vertical (Z) directions (due to the mass loading of the system), static analyses were preformed along both the axes. For the lateral load, the deflection was calculated to be 0.0014 inches while the vertical load resulted in a deflection of 0.0013 inches. In both cases, the load was assumed to be uniformly distributed over the foam.

#### 3. Foam Crushing - Dynamic

As part of the preliminary analysis, an estimate of the dynamic response of the system was made. Relating the potential energy associated with the 30 ft. drop height,  $h_0$ , and the kinetic energy at impact, the impact velocity, V, can be calculated from:

$$\frac{1}{2} (MV^2) = Mgh_0$$

giving

$$V = (2gh_0)^{\frac{1}{2}}$$

where M is the mass of the system and g is the acceleration of gravity  $(386 \text{ in/sec}^2)$ . For the 30 ft. drop height, the velocity was calculated to be 527 in/sec.

To determine the dynamics of the CAMPACT on impact, it was necessary to determine the deflection, duration and acceleration of the response. The displacement was calculated by equating the kinetic energy at impact to the energy absorbed by the crushing of the foam. For this analysis, it was assumed that the foam behaved like a rigid, perfectly plastic material, and the deflection is calculated by using

$$\delta = Mgh_{o}/(\sigma_{y}A-Mg)$$

where  $\sigma_{\mbox{\scriptsize y}}$  is the yield stress of the foam and A is the area of foam in compression.

From a free body diagram, the acceleration of the system was calculated using

$$a(g's) = \sigma_y A/Mg - 1.0$$

It was then necessary to determine the duration of the pulse. As for the calculation of the deflection, a constant deceleration, based upon crushing of the foam was assumed. The resulting pulse duration is given by:

$$t = (2h_0/a^2g)^{\frac{1}{2}}$$

Table 3 summarizes the results obtained from this preliminary analysis. One important fact learned was that it is not likely that the foam will lock up during a 30 ft. drop.

### 4. Buckling

(,

A consideration in the analysis of the system was the potential for buckling of the members of the inner frame during the impact. Estimates of both the buckling loads and the yield loads of these elements were made including the potential for a load offset. From this analysis, it was determined that the buckling loads of the system were significantly higher than the yield loads. Since this was the case, buckling of the members was not considered in the finite element analyses. Also, the buckling loads will be higher than those calculated due to the added restraint of the containment liner and the foam on the frame members. Appendix A gives buckling loads for some members as part of the calculation to determine the crushing strength of

the CAMPACT. These calculations also show that buckling loads for the members exceed their yield strength, without consideration of lateral support which is provided by the liners and foam. Some moments will clearly be created at the ends of some compression members during the impact event but we believe that these will be adequately reacted by the liner and foam.

Table 3. Preliminary Dynamic Foam Crushing Results \*

## Longitudinal Impact

Foam Area =  $92.38 \times 80.38 = 7425 \text{ in}^2$ Weight = 22583 lbMass =  $22583/386 = 58.505 \text{ lb-sec}^2/\text{in}$   $\delta = (22583 \times 360)/(140 \times 7425 - 22583) = 7.99 \text{ in}$ Percent Crush = 7.99/36.0 = 22%Peak Acceleration =  $140 \times 7425/22583 - 1.0 = 45 \text{ g's}$ Duration =  $(2 \times 360)/(45^2 \times 386)^{\frac{1}{2}} = 0.0304 \text{ sec}$ 

## Lateral impact

Foam Area =  $92.38 \times 236.3 = 21829 \text{ in}^2$   $\delta = 2.68 \text{ in}$ Percent Crush = 2.68/7.31 = 37%Peak Acceleration = 134 g'sDuration = 0.0102 sec

#### Vertical Impact

Foam Area = 80.38 x 236.3 = 18993 in<sup>2</sup> 6 = 3.08 in Percent Crush = 3.08/7.56 = 41% Peak Acceleration = 117 g's Duration = 0.0117 sec

\*Note that the values given in Table 3 assume that energy is absorbed only by the foam. Additional energy absorption by other components in the CAMPACT will shorten the duration of the impact event.

## 5. Static Crushing Strength

Conservative estimates of the static crushing strength of the CAMPACT were made for the assumption that the structure was loaded by two parallel rigid plattens. It is clear from the analyses, included as Appendix A, that the outer frame will collapse first and that the final crush strength is determined by the inner frame and surrounding foam. The crush forces, computed for longitudinal and vertical loads, are:

longitudinal----852,000 lb vertical-----2,310,000 lb

## D. Longitudinal Impact

### 1. Model Development

#### a. Finite Element Grid

As noted in Section I, symmetry conditions were imposed to reduce the size of the finite element models developed for analysis with the ADINA computer program. For longitudinal impact, vertical and horizontal planes of symmetry were taken along the longitudinal axis of the structure. To reduce the model further, only the front part (the door end) of the structure was modeled explicitly. The rear end was represented by the addition of lumped masses to the front part of the structure. Plastic deformations were not expected in the rear of the structure, and the local dynamic motions of the neglected part would have little effect on the deformations near the door. Other simplifications and justification for their use are:

\* Neglect of the outer frame--The assumption here is that motions of the inner frame occur independently from the outer frame for longitudinal impact. We believe that is a good assumption for simultaneous impact between the striking surface of the CAMPACT and the rigid surface. Any tendency of the CAMPACT to rotate from the vertical is already eliminated by the boundary conditions placed on the planes of symmetry. Further, the contact surface between the structural foam and the outer frame is smooth. The bond strength at this contact surface is unknown and slippage could occur. If slippage does not occur, then this assumption is equivalent to postulating that the outer

frame and foam translate forward during impact at the same rate as the inner frame. Of course, loads from the outer frame are transferred directly into the outer door frame assembly during longitudinal impact.

- \* Neglect of the foam on the sides and top of the inner frame—
  For longitudinal impact, the only function of the foam on the sides and top of the inner frame would be to transfer load from the inner frame to the outer frame if differential motions occurred between the two components. For the reasons cited above, the outer frame was neglected, and so the foam was neglected also. Neither its mass or its stiffness was included.
- \* Neglect of the containment liner stiffness and strength—Stiffness of the liner could be quite high in shear, if it does not buckle, but quite low in compression. This phenomenon is not easily represented in the finite element model. Because the primary response during longitudinal impact is expected to be compression, its contribution to the stiffness and strength of the inner frame was neglected. Its mass was included in the model.
- \* Neglect of the puncture panel in the outer door assembly—
  The puncture panel should absorb little energy during the
  longitudinal impact and should not interfere with crushing of
  the foam by longitudinal translation of the inner frame. It may
  cause the layer of foam between the panel and the door to crush
  first, but it should not prevent crushing of the foam below the
  panel.

\*Neglect of pallet response within the CAMPACT--The assumption of rigid body motion of the pallets during impact is a reasonable assumption for the longitudinal analysis. This assumption should produce high (conservative) loads on the inner door. Also, to have included the response of the pallets in the analysis, and still have modeled the door region in detail,

would have increased the finite element model to a size which would have exceeded our current computer resources at SwRI (with the existing heavy utilization of the computer facilities, it would make run times unbearable). Further, it did not make sense to include the pallet response and ignore the stiffness of the blocking, for which we had no information. Thus, the pallets and blocking were included in the model as concentrated masses, distributed over the inner door.

An outline of the model developed for longitudinal impact of the CAMPACT is shown in Figure 11. It represents approximately one-quarter of the exterior door (the foam) and one-twelfth of the inner frame. The top and right sides of the model are longitudinal planes of symmetry. Only the front bay of the inner frame of the CAMPACT is described by finite elements. Lumped masses were added to the back of the front bay to represent the top two bays. Figure 12 shows more detail of the frame. The elements have been reduced (shortened) for clarity, the beams have a width dimension, and trusses are represented as lines. Ten beams were used to describe the inner frame adjacent to the door.

The door is shown in Figure 13. Beams were used to describe the door frame and triangular shell elements represented the honeycomb door. Bolts were inserted between the beams of the inner frame and door to join the two components together. This is shown in Figure 14.

To complete the geometry of the model, three-dimensional solid foam elements were added to the front of the door. The block of foam elements is shown in Figure 15. There are three elements in the longitudinal (crush) direction and six elements in the two transverse directions, for a total of 108 foam elements. The width and height of the foam block are greater than the door. This is seen more easily in the outline of Figure 11, which shows the location of the door relative to the foam. Constraint equations were used to couple the door to the foam in the longitudinal (y) direction.

Table 4 summarizes the elements used in the ADINA model. All elements were specified as nonlinear with both material and geometric nonlinearities permitted. After eliminating all boundary and dependent degrees of freedom (dof), the model had 702 equations. After optimization, the mean half bandwidth was 125.

()




Figure 11. Outline of the Longitudinal Model





Figure 12. Inner Frame - Longitudinal Model



MODEL Z

Figure 13. Door - Longitudinal Model




Figure 14. Inner Frame, Door and Bolts - Longitudinal Model




Figure 15. Foam - Longitudinal Model

# Table 4. Elements and Nodes for the Longitudinal Model

Fram	<u>e</u>	
	3-D trusses3-D rectangular beams (off-set)1	
Door		
	3-D rectangular beams (off-set)	
Bolt	<u>s</u>	
	Corner: 3-D circular beam	2
Foam		
	3-D 8-noded solid elements10	)8
Node	<u>s</u>	
	Total38	14
	To do non do not	10

#### b. Concentrated Masses

ADINA computes the masses of the elements in the grid and, for this problem, concentrated the masses at the nodal points. In addition to the element masses, concentrated masses were added to represent the internal equipment (pallets, blocking and floor roller assembly) and missing parts of the structure. The mass of the containment liner was added in a rational manner to the nodes of the inner frame (see Figure 12). These masses were quite small. The mass of the two upper bays of the inner frame were added to the upper corner node of the inner frame.

All internal masses were added to the door. One half of the mass of the floor roller assembly (600 lb) was added uniformly to the bottom row of nodes on the door (see Figure 13). Placing all of the roller mass on the door is somewhat conservative because the roller is wedged laterally against the sides of the inner frame; however, slipping will most certainly occur and this will represent the worst-case loading condition for the door. Mass of the pallets and blocking was distributed evenly to the remaining nodes of the door. This mass was estimated to be 11,300 lb, 10,800 lb for the eight pallets and 500

lb for the blocking. One-fourth of this weight was concentrated (in mass units) on the door. In all, 8844 lb of mass was added to the model at 50 nodal locations.

## 2. Impact and Boundary Conditions

As discussed previously, an idealized impact condition was assumed, whereby the end of the CAMPACT struck uniformly against the rigid surface. To achieve this condition, a uniform velocity of 527 inches per sec was applied to all nodes of the model. This velocity corresponds to a drop height of 30 ft. Figure 16 shows the velocity vectors applied to the model. Velocities at the impacting surface are also shown in the figure, but these were eliminated by constraining the nodal degrees of freedom (dof) in the y-direction on the striking surface.

The translational dof of the striking surface are shown graphically in Figure 17. Small lines at the nodal locations indicate the dof directions in which motion was permitted. Note that no motion is allowed in the ydirection on the impacting surface. The only other boundary conditions applied to the model were those of symmetry applied to the top surface (horizontal mid-plane) and right side (vertical mid-plane) of the CAMPACT. On the top surface z-displacements, x-rotations and y-rotations were restrained; on the right side x-displacements, y-rotations and z-rotations were restrained.

## 3. Solution Results

The model was solved using the ADINA computer code. A direct integration of the equations of motion was performed by a Newmark integration procedure. Equilibration iterations were performed at each integration time step of 0.0001 sec, and the stiffness matrix was reformulated at every third (and sometimes every) time step. The integration was carried out to a time of 0.025 sec. All of the steel components in the model, except for one bolt, had returned to a totally elastic state at 0.022 sec. At 0.024 sec, all steel components were elastic, and at 0.025 sec, only two foam elements were still showing plasticity, one at one integration point and the other at two integration points.




Figure 16. Velocity Vectors - Longitudinal Model




Figure 17. Translational Degrees-of-Freedom at the Impact Surface of the Foam - Longitudinal Model

Four points on the door are plotted out to 0.022 sec in Figure 18\*. At this time, nodal points 118 and 247 (on the horizontal centerline) have reached their peak displacements. Nodal points 10 and 166 (on the bottom of the door) reach their peaks at 0.023 sec. Rebound of all points on the door and frame is occurring after 0.023 sec. Some distortion of the door is apparent, and some local yielding of the door frame occurred at the horizontal centerline. This result and others are discussed on a component by component basis in following paragraphs.

Inner frame--Yielding in the inner frame occurred in the longitudinal truss member of Figure 12 and in the beams adjacent to the door. The axial residual compressive strain in the truss member reached 0.08%, which indicates that it just yielded. As shown in the preliminary analyses of Section II.C.3, buckling of the frame should not occur for small plastic straining.

Distortion of the inner frame around the door occurred, just as it did for the door. This was indicated by Figure 18 discussed previously. Distortions in the frame were exaggerated in the model by compressive yielding of the bolts which joined the door and the frame. This yielding was a consequence of the finite element model and will not occur in the CAMPACT. In the model, the bolts were allowed to compress; whereas, in the CAMPACT, the inner frame and door frame are in direct contact and bolt compression is prevented. In spite of the exaggerated distortion permitted by the model, the residual plastic strain in the frame at the door reached only 0.26%, which is small. It should be no more than that which occurred in the door.

<u>Door</u>--Distortions in the door, indicated by Figure 18, caused minor yielding of the door frame to occur at the horizontal centerline. Residual plastic strain in the door reached only 0.02% at this location, which is insignificant. The load on the door which produced these distortions was caused by the corner loads from the frame and the loads at the bottom of the door from the roller assembly. No yielding occurred in the honeycomb door panel.

<u>Bolts</u>--As noted above, axial compression of the bolts occurred which would not occur in the CAMPACT. Because this behavior was not prevented in the model, compression strains in the corner bolt reached 6.9%. Of this

<sup>\*</sup>Figure 18 was drafted in final form before the final calculations from 0.022 sec to 0.025 sec were made.




Figure 18. Displacements of the door after impact in the y-direction

Longitudinal (y) Displacements (inches)

strain, 5.4% was produced by axial compression and 1.53% by bending. These strains were caused by simplified modeling of this region of the CAMPACT and we estimate that no plastic straining of the bolts would have occurred in the CAMPACT during longitudinal impact. No tension occurred in any of the bolts, and smaller strains were produced in bolts away from the corner. The next highest strains occurred in the bolts adjacent to the corner and they reached 2.7%. Bolts on the centerlines of the CAMPACT did not yield, nor did those adjacent to them.

Foam--Full plasticity occurred in all foam elements. Maximum residual plastic strains reached 23.4%. They occurred in elements immediately below the corner of the door. Nominal strains in the foam were in the range of 17-19%. The foam yields at 4% strain, and lockup occurs at about 50% strain, so the foam can absorb considerably more energy than it absorbed during this simulated 30 ft. drop.

<u>Door Seal</u>—No separation of the door frame and inner frame will occur during longitudinal impact. All bolts are placed in compression by the impact which will serve to increase the compression between the two members; however, relative rotation of the door and frame can and did occur which affects the compression in the seal. The amount of relative rotation in this analysis reached a maximum value of 0.0194 radians. From the bolt location to the center of the seal is about 2 inches, so the maximum separation at the seal caused by this rotation would be about 0.0388 inches. This separation is 16.2% of the initial seal compression [2]; thus, no seal leakage should occur as a result of longitudinal impact produced by a 30 ft. drop.

# 4. Estimate of Impact Crush Strength

Using the results of the ADINA calculations, an equivalent crush force was determined for the CAMPACT. It can be used to evaluate impact of the CAMPACT, but only under very similar conditions. The calculations, reported in Appendix B, equate the kinetic energy at impact to the deformation energy of the CAMPACT. Using the maximum deformation computed in the CAMPACT by the ADINA analyses, the equivalent crush force was found to be  $1.27 \times 10^6$  lb. This value is just slightly higher than the crushing strength of the foam in the end of the CAMPACT, which is  $1.25 \times 10^6$  lb. Thus, most of the energy absorbed by the CAMPACT during longitudinal impact was absorbed by the foam.

## E. Lateral Impact

## Model Development

## a. Finite Element Grid

As noted in Section I symmetry conditions were imposed to reduce the size of the finite element models developed for analysis with the ADINA computer code. For the lateral impact model, a vertical plane of symmetry normal to the longitudinal axis was taken at the midpoint of the inner frame. Figure 19 shows a line drawing of the model used for the lateral impact. The impact surface is on the left side of the figure while the door is forward. For this figure the viewpoint is forward, to the left and above the CAMPACT. This viewpoint will be utilized throughout this section. Note that the CAMPACT is oriented as it would be in service. The various elements of the model can be seen in Figure 20. This drawing is complex and the various elements are shown separately in Figures 21 to 24.

The front half of the inner frame was modeled as shown in Figure 21. All frame members except those at the door were represented by nonlinear 3-D truss elements. It was felt that their primary load carrying capabilities would be axial. In most cases, bending would be prevented by the proximity of the foam elements. This approximation allowed for a reduction in model degrees of freedom. Various dof associated with the nodes of the inner frame were coupled using multiple-point constraints. These constraints were applied in regions where the stiffness was small and would tend to produce numerical instabilities during the dynamic nonlinear analysis. Different constraints were utilized for the static and dynamic solution. The result of the dynamic constraints is that the frame surface will act as a unit with limited local deformation. As with the longitudinal model, the region near the door was described in the most detail. The frame members in this region were represented by 3-D beam elements.

Figure 22 shows the door used in this model. The honeycomb panel was represented by triangular plate bending elements. The plate elements were assumed to remain elastic during the analysis. Calculations showed that the bending stiffness of the honeycomb was dominated by the thickness and strength of the face plates themselves. The core provided little resistance to bending except to separate the face plates. The 4 in. by 6 in. edge beam of the door was modeled using beam elements. The size and material properties of these elements were adjusted to match the bending about




Figure 19. Outline of the Inner Frame and Foam - Lateral Model





Figure 21. Trusses and Beams of the Inner Frame - Lateral Model



RODEL

Figure 22. Door - Lateral Model




Figure 23. Inner Frame, Door Frame and Interconnecting Bolts - Lateral Model




Figure 24. Foam Elements - Lateral Model

the two axes of the member. The resulting member had an axial stiffness greater than the CAMPACT.

Attachment of the door to the inner frame was again made using beam elements. For this model, the four corner bolts were modeled as in the CAMPACT itself. Only three beams were utilized to model the nine bolts actually present on each side of the door in the CAMPACT. Since for this model the primary action of the bolts would be in shear, the resulting beams were proportioned to have the correct area, not the correct bending stiffness. In the CAMPACT, the centerlines of the door and inner frame members are seven inches apart. For the longitudinal model, this distance was maintained in the model. For the lateral impact model, the distance was reduced to one inch. It was felt that this would more accurately represent the actual conditions. Some details of the door-to-inner-frame connection can be seen in Figure 23.

The foam elements utilized in this model are seen in Figure 24. Only the foam on the side where the impact occurred and on the top and bottom was modeled. The foam on the opposite side from the impact was ignored because the material has little resistance to tension. The top and bottom foam was modeled because of the expected three-dimensional response of the system. The foam forward of the door was also ignored since it will not significantly contribute to the energy absorption characteristics of the lateral model. In this model, only one element was used through the thickness of the foam in the direction of impact. To limit numerical instabilities, a token mass of 0.01 lb-sec<sup>2</sup>/in was added to all foam nodes on the upper and lower surfaces.

In addition to the approximations described above, the following assumptions were made concerning the model.

\* Neglect of the outer frame--The basic assumption here is that the energy at impact associated with the outer frame, puncture panels and the outer skin will be absorbed by local deformation of the outer frame. In addition, motions of the inner frame occur independently from the outer frame for lateral impact. We believe that is a good assumption for simultaneous impact between the striking surface of the CAMPACT and the rigid surface. Further, the contact surface between the structural

foam and the outer frame at the puncture panel is smooth. The bond strength at this contact surface is unknown and slippage could occur. If slippage does not occur, then this assumption is equivalent to postulating that the outer frame and foam translate laterally during impact at the same rate as the inner frame.

- \* Neglect of the containment liner stiffness and strength—
  Stiffness of the liner could be quite high in shear if it does
  not buckle but quite low in compression. This phenomenon is not
  easily represented in the finite element model. Because the
  primary response during lateral impact is expected to be
  compression, its contribution to the stiffness and strength of
  the inner frame was neglected. Its mass was included in the
  model.
- \* Neglect of the puncture panel system--The puncture panel should absorb little energy during the lateral impact. It is assumed that the kinetic energy associated with this mass will be absorbed by the outer frame.
- \* Neglect of pallet response within the CAMPACT--The assumption of rigid body motion of the pallets during impact is a reasonable assumption for the lateral analysis. This assumption should produce high (conservative) loads on the side wall. Further, it did not make sense to include the pallet response and ignore the stiffness of the blocking, for which we had no information. Thus, the pallets and blocking were included in the model as concentrated masses, distributed as required.

Table 5 summarizes the elements used in the ADINA model. All elements except the door plate elements were specified as nonlinear with both material and geometric nonlinearities permitted. After eliminating all unnecessary degrees of freedom, the model had 347 equations. After optimization, the mean half bandwidth was 63.

lable 5.	Elements and Nodes for the Lateral Model
Frame	
	3-D truss elements44 3-D beam elements16
Door	
	3-D beam elements16 Triangular plate elements32
<u>Bolts</u>	
	Corner: 3-D circular beam elements 4 Sides: 3-D circular beam elements12
Foam	
	3-D 8-noded solid elements24
Nodes	
	Active109

#### b. Concentrated Masses

ADINA computes the mass matrix of the model from the lumped masses of the elements and concentrated masses at the nodal points. The concentrated masses were added to represent the internal components (pallets, blocking and floor roller assembly) and elements ignored in the stiffness formulation. For this model, the locations of the added masses in the three principal axes were different. This reflects our estimation of how they would be distributed during the lateral impact. The mass of the containment liner was added to the nodes on the inner frame in proportion to the tributary area of each node. This mass was associated with all three axes. One half the mass of the roller floor (600 lb) was added uniformly to the bottom row of nodes on the door in the longitudinal direction, along the intersection of the side wall and floor for the lateral direction and distributed over the floor for the vertical direction.

Mass of the pallets and blocking was distributed over the side for lateral response, over the door for longitudinal response, and over the floor for vertical response. For the vertical direction, the load was distributed uniformly over the floor. For the longitudinal and lateral directions, the load was distributed linearly from the floor (1.75 times the average) to the top (0.25 times the average) on the side and door, respectively.

An apparent error occurred during the automatic generation of the concentrated masses which resulted in less mass and lower than desired gravitational forces in the static analyses of the lateral model. The error was found and corrected before the impact calculations were performed. For the static analyses, the amount of added concentrated mass for the three axes relative to the required mass was: X-axis 61%, Y-axis 94% and Z-axis 78%.

# 2. Impact and Boundary Conditions

As discussed previously, an idealized impact condition was assumed, whereby the side of the CAMPACT struck uniformly against a rigid surface. To achieve this condition a uniform velocity of 527 in/sec was applied to all nodes of the model. This velocity corresponds to a drop height of 30 ft. Figure 25 shows the velocity vectors applied to the model. Velocities at the impacting surface are also shown in the figure, but these were eliminated by constraining the nodal dof in the x-direction on the striking surface.

The translational dof of the model are shown graphically in Figure 26. Small lines at the nodal locations indicate the dof direction in which motion was permitted. Note that no motion is allowed in the x-direction on the impacting surface. The only other boundary conditions applied to the model were those of symmetry applied at the centerline of the CAMPACT. On this surface, the y-displacement, x-rotation and z-rotation were restrained at each node.

In addition to restraints, some of the the nodes were coupled to other nodes along specific axes. These were primarily on the side opposite the impact where the trusses were not capable of carrying a load in the x-direction. For these nodes, the x-response was coupled to the appropriate x-responses at nodes that did have a component of stiffness in the x-direction. Additional nodal restraints were added to the dynamic model as described previously.




Figure 25. Velocity Vectors - Lateral Model

Ć.,




Figure 26. Translational Degrees-of-Freedom - Lateral Model

#### 3. Solution Results

#### a. Static Results

Two different static load cases were applied to the model. They corresponded to a 1g acceleration in the lateral (x) direction and a separate 1g acceleration in the vertical (z) direction. The loads applied to the nodes for the first load case, lateral acceleration, are shown in Figure 27. These represent the concentrated masses to which the lumped masses of the elements were added. The resulting deflected shape is shown in Figure 28. Note that the deflections are multiplied by a factor of 5000 in relationship to the geometry of the model to make them visible. For the nodes on the inner frame closest to the impact surface, the average defection was 0.00059 inches with a maximum of 0.00146 inches. Making a correction associated with the concentrated masses, the preliminary analysis deflection for this direction is 0.00085 inches ( $0.61 \times 0.0014$ ), which compares favorably. There is significant local variation of the displacements which can be seen from Figure 28. These are plots of the deflected shape as seen from in front and above the model. On the back surface of the inner frame, opposite the impact surface, the displacement is more uniform with an average of 0.00121 inches and a maximum of 0.00155 inches. This indicates that there will be a variation in deflection between the impact and the opposite sides of the inner frame. One observation from Figure 28 is that there is more deflection at the bottom than at the top. This is representative of the distribution of the pallet loads and how they were applied.

A similar analysis for the vertical static load was also performed. The load (Figure 29) and displacements (Figure 30) are as expected. In this case, the loads are more uniform and so the results show less localized deformations. The average displacement was 0.0087 with a maximum at the center of the panel of 0.0179 inches. In section II.C.2, the preliminary calculation for the static deflection in the vertical direction gave a prediction of 0.0013 inches. Accounting for the reduced mass used in the static ADINA calculations (78% of the actual mass as explained in Section II.E.1.6), the corresponding prelimninary static deflection in the vertical direction would be

$$\delta_{st} = 0.78 \times .0013$$
 inches = 0.0010 inches

which compares favorably.






Figure 27. Static Load Case 1 - Lateral Model




6

a. isometric view Figure 28. Deflected Shape - Static Load Case 1 - Lateral Model



b. front view
Figure 28. (Cont'd.) Deflected Shape - Static Load Case 1 - Lateral Model



c. top view
Figure 20. (Concluded) Deflected Shape - Static Load Case 1 - Lateral Model

MODEL

DEFLS






Figure 29. Static Load Case 2 - Lateral Model



a. isometric view Figure 30. Deformed Shape - Static Load Case 2 - Lateral Model



b. front view Figure 30. (Cont'd.) Deformed Shape - Static Load Case 2 - Lateral Model





Figure 30. (Concluded) Deformed Shape - Static Load Case 2 - Lateral Model

# b. Dynamic Results

The model was solved using the ADINA computer code. A direct integration of the equations of motion was preformed using a Newmark integration procedure. Equilibration iterations were preformed at each time step of 0.00002 seconds and the stiffness matrix was reformulated at every second time step. The integration was carried out to a time of 0.0065 seconds at which time all nodes had reached their maximum negative deflection.

Deflections—The deflections of the model due to the lateral impact are extremely complex. This is due to the complex geometry of the model and the distribution of the masses from the pallets, blocking and roller. Figures 31, 32, and 33 are plots of the displacement of twelve points on the structure as a function of time. These three plots correspond to the four nodes at the corners of the first major cross member of the inner frame, the inner frame at the door, and the door itself. Of the three groups, the door demonstrates the least amount of relative deflection. This is to be expected because of the stiffness at the frame and panel elements. The relative displacement at the first major cross member resulted in significant stress in three members, Figures 34 and 35. As can be seen, the points all move at a slightly different rate and end up at different locations at the conclusion of the analysis.

An important parameter when considering the response of foam to dynamic loads is the percent of crush. This is the amount of deflection in relationship to the original depth of the foam. Figure 36 gives the maximum plastic strain in the six large foam elements on the impact face. This strain is calculated based on a Von Mises stress which is always positive. Because of this, the plot was stopped when the elements went into tension, effectively unloading the elements. To this plastic strain, the elastic strain, 4%, must be added to get the total strain of the element. For this model, the maximum total strain on the side face of the foam for the times considered was 19% which corresponds to the percent of crush. This is significantly below the value of 52% which is given as the lockup value for this type of foam [6]. A similar result is obtained by taking the maximum deflection at the door, 1.47 and dividing by the initial length, 7.31 inches, giving a 20% crush. In the preliminary analysis a 37% foam crush was calculated. This calculation was



Principle of Decor

CONTRACT DESCRIPTION TO PROPERTY SAFERED





Figure 31. Deflection of 1st Major Cross Member







Figure 32. Deflection of Inner Frame at Door







Figure 33. Deflection at Door






Figure 34. Strain in Truss Element on Bottom of Inner Frame at First Major Cross Member





Figure 35. Strain in Truss Element Top of Inner Frame at First Major Cross Member



Front

19

20

Top

16

17

Plastic Strain in the Foam Elements on the Impact Face Figure 36.

based on a rigid inner frame. For this model, there was significant yielding and corresponding energy absorption in the inner frame. The result was less foam crush than predicted by the preliminary analysis. See also the comments in Section II.E.4, Estimate of Impact Crush Strength.

Inner Frame--There was yielding of the inner frame truss members early on in the event, at the time of 0.0012 seconds. The majority of yielding was associated with compression in the members. Figures 34 and 35 give the strains associated with three truss elements on the top and bottom portions of the inner frame at the major cross member near the impact surface. Elements 1 and 6 are the lateral members and the remaining four are the diagonal members. Note that due to relative displacement differences these strains have not leveled off. The maximum strain at the end of the event was located in truss 6, 5.9% of which 5.7% was residual plastic strain. This value is significantly below the 40% ultimate strain level defined for these stainless steel trusses (Table 1). There was some yielding of the inner frame at the door along the edge closest to the impact surface. The maximum plastic strain was 0.2%. It is felt that the majority of this yielding is due to the conservative approximation made in the modeling in this region. The first approximation was the fact that the nine bolts on each edge were modeled using only three beam elements. In addition, the foam elements were attached to these beam elements only at the corners and the midpoints. These two approximations resulted in excessive load transfer between the door and the inner frame at the corners and the midpoints. A more detailed model with all bolts included and a finer mesh for more uniform load transfer between the foam and the truss elements, would most certainly have produced much less yielding of the inner frame. A "30 ft" lateral impact test of the CAMPACT should produce no significant yielding of the inner frame at the door.

Door--The frame members around the door did not yield at any time during the analysis; however, some problems were encountered in the modeling of the honeycomb portion of the door. In the analysis, the elements were assumed to remain elastic. A check of the membrane forces in some of the elements indicated that local yielding would have occurred. Assuming that the membrane forces are resisted only by the two stainless faces, 0.1875 inches thick each, the allowable force per unit length, without yielding, was calculated to be  $1.125 \times 10^4$  lb/in. Local forces up to three times this value were calculated during the analysis. These conservative levels are in part

due to the approximations described previously which gave excessive loads at the midpoints.

To estimate the overall membrane forces consider the deformation pattern of the four nodes given in Figure 33. There is little relative motion between the two nodes on the top and bottom surfaces at the door. Any relative deflection of these points would tend to produce compression in the face plates. The primary distortion which can potentially produce yielding of the door will be the relative motion between the top and bottom surfaces. For this condition the stress is given by

$$c_{xy} = \frac{Eu}{(1+v)2b}$$

where u is the relative displacement (0.1942 inches) and b is the height of the door (89.38 inches). For this case the stress was calculated to be 25,200 psi. The yield stress for stainless is 30,000 psi; therefore, there will most likely be no overall yielding of honeycomb door. There may be some localized stresses in excess of 30,000 psi but they will not be as high as those indicated in the analysis.

Bolts--There was significant yielding of the bolts attaching the door to the inner frame during the event. The first to yield were the corner bolts which were represented at their true size in the model. Due to the approximations made, their area could have been increased slightly with a corresponding decrease in the area of the inner bolts. The maximum residual stresses in the four corner bolts according to the analysis were 17%, 9%, 26% and 35%. The highest value corresponds to the upper corner closest to the impact surface. This can be seen by comparing Figures 32 and 33 which show the displacements of these points as a function of time. The maximum relative displacement at this point is 0.101 inches occurring for t=0.0047 seconds. The majority of the stress in the bolt is caused by the moments resulting from the relative lateral displacement of the bolt ends. Clearly, the high strains in the corner bolts were caused by the conservative modeling of this region, i.e., a free bolt length of 1 inch and a model which transferred most of the loads through the corner bolts and the bolts at the centerline.

The stresses and strains in the other bolts calculated by this analysis are also conservative. Calculated residual plastic strains, up to 170% at the centerline bolts, are not realistic. For all the bolts, the

failure strain is given as 50%. As for the corner bolts, the reasons for these conservative results are the approximations made in the modeling. The nine bolts on each side were represented by only three elements whose diameter was defined by matching the appropriate shear area rather than the bending stiffness. If the bending stiffness were matched, the diameter of the bolts would be larger resulting in lower stress and strains. Also, the attachment of the inner frame at the door to the foam, only at the midpoints and ends, loaded the midpoint bolts excessively. As an estimation of the expected stress and strain on these bolts, the assumption will be made that the stress and strain in the corner bolts are correct. (In reality they will probably be lower than calculated as described above.) If we then assume that the displacements of, or loads at, the other bolts can be calculated by interpolation between the corner bolts, corresponding stresses and strains in the side bolts can be estimated.

We will assume that bolt strains are directly proportional to the relative lateral displacements of the bolt ends, i.e., end rotations will be ignored. This lateral sway condition, shown in Figure 37, produces bolt bending strains which are directly proportional to  $\Delta$ , the relative displacement of the ends, or

$$\varepsilon_{\text{max}} = \frac{3d\Delta}{L^2}$$

Where d is the bolt diameter.




Figure 37. Bolt in lateral sway

The relative displacement in the impact direction between the inner frame and door at the corners can be estimated from Figures 32 and 33. At the four corners the maximum relative values are approximately:

Top left (UX
$$_3$$
 - Ux $_{23}$ ): 0.0875 in. Bottom left (UX $_{83}$  - UX $_{76}$ ): 0.1625 in. Top right (UX $_{48}$  - UX $_{74}$ ): 0.0875 in. Bottom right (UX $_{105}$  - UX $_{76}$ ): 0.125 in.

At the bottom left corner bolt the maximum strain is thus

$$\varepsilon_{\text{max}} = \frac{3d\Delta}{1^2} = \frac{3(1.0 \text{ in.})(.1625 \text{ in.})}{(1 \text{ in})^2}$$

$$= 0.4875$$

This value is higher than the strain of 35% predicted by ADINA and suggests that end rotations occurred that reduced the strain. At the side bolt adjacent to the bottom left corner bolt, a linear interpolation of relative displacements gives:

$$\Delta = .0875 + \frac{0.1625 - 0.0875}{89.38} \times 80.44 = 0.155 \text{ in.}$$

The corresponding strain for the bolt is

$$\varepsilon_{\text{max}} = \frac{3(0.75 \text{ in.})(.155 \text{ in})}{(1.0)^2} = 0.349 < \varepsilon_{\text{ult}} = 0.50$$

This is the most highly loaded side bolt, and this conservative analysis suggests that the bolt will not exceed the ultimate strain for the material. A more realistic, but still conservative, estimate of the stress is obtained if we reduce this value by the ratio of the ADINA calculated strain for the corner bolt to that estimated by this procedure. The reduced value is

$$\varepsilon_{\text{max}} = 0.349 \times \frac{0.35}{0.4875} = 0.25$$

On the basis of these calculations the maximum expected bolt strain would be that of the most highly loaded corner bolt or 35%. This strain level is quite high for a bolt, even though it is less than the ultimate strain of 50% for the bolt material. Thus, we believe that the design is marginal, even though it has survived side impact from a 30 ft. drop [2]. A modest redesign of the mating surfaces between the door and the inner frame could relieve the shear load on the bolts which led to the high strains observed.

Foam--All the foam elements on the side face of the CAMPACT yielded during the impact event. The maximum deflection was shown previously to be 1.47 inches with a corresponding percent crush of 20%. The region of foam at the floor of the CAMPACT was subjected to the most crushing as would be expected from the mass distribution. Some of the elements on the top and bottom surfaces yielded due to localized deformations.

Door Seal--If there is significant yielding of the bolts, precompression in the seal may be affected; however, at the corner nodes, the longitudinal differential deflection between the door frame and the inner frame all tend to increase the compression in the seal. The maximum relative displacement is 0.0036 inches. The maximum relative rotation is 0.00083 radians which, assuming a 2 inch distance from the center of rotation to the seal, would produce a relative displacement of 0.0017 inches. From Reference 2 the initial compression of the seal is 0.24 inches. Therefore, the seal will not be broken at the corner due to the calculated deflection. We expect this to be true along the sides of the door as well.

#### 4. Estimate of Impact Crush Strength

An eqivalent crushing force for lateral impact of the CAMPACT was estimated as shown in Appendix B. Because substantial deformation occurred in the inner frame as well as in the foam for lateral impact, calculations were made to bound the crush force. The upper bound considers deformation in the foam only and the lower bound considers total back face to front face crush of the CAMPACT. The calculated bounds are:

$$2.43 \times 10^{6}$$
1b  $\leq F_{cru} \leq 6.3 \times 10_{6}$  1b

#### F. Summary of Results

#### Longitudinal Impact

The ADINA calculations performed in this study have shown that the CAMPACT can survive a 30 ft. longitudinal drop without failure. Here, failure is defined as breaching the inner containment boundary, either through rupture of the containment liner or loss of door seal. Neither of these events is likely to occur for the conditions analyzed. Based on a conservative model of the door-to-frame connection, maximum separation on the seal was only 16.2% of initial seal compression, resulting in no loss of contact.

For a higher drop height, forces in the inner frame and door will remain at about the same level until lockup occurs in the foam at a strain near 50%. This means that approximately 50% of the energy absorbing capacity of the foam was utilized in the 30 ft. drop. Impact energy will increase in direct proportion to the drop height, so the calculations indicate that the CAMPACT should survive a 50 ft. longitudinal drop without foam lockup. At a drop height of 60 ft. some lockup of the foam will start to occur.

#### 2. Lateral Impact

From the conservative analysis performed, it is not possible to give a definitive answer as to the survivability of the CAMPACT when subjected to a 30 ft drop onto an unyielding surface. A question arises as to the performance of the bolts connecting the door to the inner frame. The analysis indicates significant yielding of the bolts, yet a more realistic or detailed model might well reduce bolt strains. Thus, we believe that the design is marginal for lateral impact from a 30 ft. drop, but that a minor redesign, to relieve bolt shear, would make the CAMPACT acceptable for these conditions.

The percentage of crush in the foam for the 30 ft. drop was only 20%. Forces in the frame and door should remain at about the same level until lockup does occur at a crush of 50%. Since the impact energy is directly proportional to the drop height, calculations indicate a drop height of 75 ft. before lockup. This estimation indicates that, if the bolt shear loads are reduced, the CAMPACT has an excellant chance of surviving even higher drops, prehaps as high as 60-75 ft. A more detailed model, which represents all bolts and more realistic coupling between the foam and the truss members, can provide useful insight for CAMPACT redesign in the door region and for CAMPACT response to higher drop heights.

#### III. ESTIMATES OF M55 ROCKET FAILURE INSIDE THE CAMPACT

#### A. Longitudinal Impact

An estimate of rocket failure (failure of the agent canister) within the CAMPACT can only be postulated from the pallet analyses of Reference 1. In that document, an analysis of the rocket was made which simulated a longitudinal drop of the CAMPACT from a height of 40 ft. Results of the calculation showed that the rocket would survive and that the the strain level in the foam of the CAMPACT would reach 37.5%. This value of strain is somewhat higher than the 23.4% calculated for the CAMPACT in this report.

One explanation for this difference is that in the ADINA calculations for the CAMPACT, internal foam elements saw a triaxial state of stress; whereas, in Reference 1, a uniaxial representation for the foam was used. The triaxial state of stress effectively increased the stress level at which yielding of the foam occurred. As an upper bound, the effective compressive yield stress could be 41% higher than the uniaxial yield stress, for a Poisson's ratio of 0.3 as specified for the foam. Coupling between the rocket and the foam could also account for some of the difference observed.

It was also assumed in the analysis of Reference 1 that the loading from the top pallet (they are stacked end to end in the CAMPACT) would not crush the wooden longitudinal stringers and fiberglass launching tubes in the bottom pallet and transfer loads directly into the rocket. Calculations were made and included in an appendix of Reference 1 which shows that this is a valid assumption. Thus, we are confident that the rocket will survive a 30 ft. or 40 ft. longitudinal drop within the CAMPACT.

The effects of the CAMPACT on the survivability of the pallet for lateral impacts were not addressed.

#### IV. CONCLUSIONS AND RECOMMENDATIONS

#### A. Conclusions

From the analyses of the CAMPACT described in this report the following conclusions were drawn:

- (1) The CAMPACT will survive a longitudinal drop of 30 ft. without failure:
- (2) Based on the results computed for the 30 ft. drop, it is highly probable that the CAMPACT will survive a longitudinal drop from 40 ft. and likely that the CAMPACT will survive a longitudinal drop of 50 ft.; however, calculations for the 40 ft. and 50 ft. drops were not made;
- (3) Within the CAMPACT, the M55 rockets will survive a longitudinal drop greater than 40 ft.;
- (4) From the analyses performed, it is not possible to accurately predict survivability (or failure) of the CAMPACT when subject to a lateral drop of 30 ft; however, the analyses were conservative, which is confirmed by the fact that a prototype CAMPACT has survived side impact from a 30 ft. drop. We have not had access to detailed results from the CAMPACT drop tests. From such data one might be able to conclude that the CAMPACT has a high probability of surviving lateral impacts from 30 ft. drops.

#### B. Recommendations

The analyses performed in this study were based on our best efforts within the constraints of time, dollars and information available to us. Clearly, refinements to the analyses can be made and additional conditions can be examined to provide information on edge impact, corner impact, etc. The one aspect of the problem most in need of study is the coupled response of the CAMPACT and pallets. Coupled response was not addressed in this study, and we suggest that such calculations be made if failure of the M55 rocket within the CAMPACT is a critical issue to be resolved. This could be done for longitudinal and lateral impact by expanding the existing models. To study edge or corner impacts would require extensive changes to the existing models, but the information data base that we have accumulated would still be

applicable. Additional analyses for lateral impact with a more detailed model, as described previously, should be made. We further suggest that redesign of the door/inner frame connection be considered to reduce the high bolt shear loads observed in the calculations for lateral impact.

#### V. REFERENCES

- 1. Stewart, S. E. and Cox, P. A., "Nonlinear Dynamic Response Analysis of 115mm Chemical Rocket Packing Impact," Draft Final Report, SwRI Project 06-8461-001, April 1985.
- 2. Personal communications between SwRI staff and H&R Technical Associates personnel.
- 3. Telephone conversation between P. A. Cox, SwRI and Bob Burgoyne, General Atomic, February 25, 1985.
- 4. "ADINA, A Finite Element Program for Automatic Dynamic Incremental Nonlinear Analysis," Users Manual Report AE81-1, ADINA Engineers, Inc., September 1981.
- 5. The "Gifts" System, Graphics-oriented Interactive Finite Element Time-Sharing System Version 5.03 Users Reference Manual, April 17, 1981, University of Arizona.
- 6. Patel, M. R. and Finnie, I., "Structural Features and Mechanical Properties of Rigid Cellular Plastics," <u>Journal of Materials</u>, JMLSA, Vol. 5, No. 4, December 1970, 909-932.
- 7. ASTM Standards (Various for different materials).
- 8. Deutschman, A. D., Michel, W. J. and Wilson, C. E., <u>Machine Design Theory and Practice</u>, MacMillan Publishing Co., Inc., New York, 1975.
- 9. Woolam, W. E., "A Study of the Dynamics of Low Energy Cushioning Materials Using Scale Models," Society of Plastic Engineers, Inc., 3rd Annual Technical Conference, Technical Papers, Vol XIII, May 15-18, 1967, Detroit, Michigan, 475-479.

APPENDIX A

CAMPACT CRUSHING ANALYSIS FOR STATIC LOADING

## CHMPART COLLAPCE/CRUSHING LOAD

THE THELAPSE LOAD/CRUHING LOAD OF THE CAMPACT WILL BE BASED SOLELY ON THE COLLAPSE LOADS OF THE TRAME MAMBERS AND FORMI. FIRST COUSIDER LONGITUDIANC LOADING.

# LONG MOINIL LONDING

THE SUTER FRAMIEWORK, SHOWN IN FIGURE 3 IN THE
FIRST.

LOADS, IT COILSISTS OF 4 MEMBERS, EACH

ONE BEING A BIN. X BIN. X D. IZ IN WALL S. STL.

TUBE THE TUBES ARE BRACED AT INTERVARS

OF 76.43 INCHES GECTION FILL MATERIAL

FRODERINGS OF THE TUBES ARE:

 $A = (3in)(3in) - (2.75in)(2.75in) = 1.4375in^{2}$   $A = \frac{1}{12}[(3)(3)^{3} - 2.75(2.75)^{3}] = 1.984in^{4}$   $A = \sqrt{\frac{1}{12}}A = 1.175in$   $A = \frac{1}{12}[(3)(3)^{3} - 2.75(2.75)^{3}] = 1.984in^{4}$   $A = \sqrt{\frac{1}{12}}A = 1.175in$   $A = \frac{1}{12}[(3)(3)^{3} - 2.75(2.75)^{3}] = 1.984in^{4}$   $A = \sqrt{\frac{1}{12}}A = 1.175in$   $A = \frac{1}{12}[(3)(3)^{3} - 2.75(2.75)^{3}] = 1.984in^{4}$   $A = \sqrt{\frac{1}{12}}A = 1.175in$   $A = \frac{1}{12}[(3)(3)^{3} - 2.75(2.75)^{3}] = 1.984in^{4}$   $A = \frac{1}{12}[(3)(3)^{3} - 2.75(2.75)^{3}] = 1.984in^{4}$ 

THE BUCKLING STREET CAN BE COMPUTED FROM TE

Copy of the permit fally by the production

2.6

$$T_e = \frac{P}{A} = \frac{C \pi^2 E}{(-/r)^2}$$

WYON C = COEFFICIENT TO ACCOUNT FOIR DEFERENT END CONDITIONS = 1.0 FOR PINNED FNOS LYPE CLENOFICHERS RATIO

C THE CONSERPROVERY ASSUME THAT THE ENDS ARE DENED WE FIND

$$\frac{\sqrt{29.5 \times 10^{3} \text{ Ps}^{3}}}{\sqrt{29.5 \times 10^{3} \text{ Ps}^{3}}}$$

$$= 61,350 \text{ Ps} 1$$

$$\frac{\sqrt{29.56} \times 100^{3} \text{ Ps}^{3}}{\sqrt{29.5 \times 10^{3} \text{ Ps}^{3}}}$$

THUS, THE YIELD STRESS / LOAD OF THE TUBES WILL BE REACHED. BECAUSE THE TUBE IS ATTACHED TO TWO MAMPRITUE PANELS WHICH INTERSECT AT 90, THE CRUSH LUMD COULD EASILY EXCEED THE YIELD LOPO; HOWEVER, FOR THIS ANALYSIS THE YIELD LOAD IC CONSERVATIVELY TAKEN AS THE CRUSH LOAD. IT IS

$$F_{TJ} = J_y A = (30,000 psi)(1.4375 u^2)$$
  
= 43,125 16

TOUR ALL FOUR TURES IN DARKLEL, THE TOTAL CRUSK

Love The OUTER FRAME IS

F== 4 x +3,3= 172,500 16

DINCE THE OUTER FRAME -AS COULAPSED, THE LONDING WILL BE TRANSFERED TO THE FORM AN MEN TO THE INTER FRAME, FOR THE ASSUMPTIM OF A RIGID NNOW TRANE, THE CRUET LOAD TOU THE FORM (BEFORE LOCK-UP) 15

F. = J.A

William

J = 140 psi A = 88.75 in x 100.75 in = 3942 in

THE RESIDENCE STREWALK THOU!

F== (140psi)(3942in2) = 1.25x10 16

OF THE FRAME CARRIES

F\_F = 140 x 36 m x74m = 501,00016

AFTUR THE FURTH LOCKS -UP , HIGH WADE MAY BE CALLY ED BY THE INDER FIRMER IT IS COMPRISO

X INTERMIC DIMENSONS OF THE OUTER FRAME FOR A SECTION! NORMAL TO THE LUNGITUDINAL AXIS

OF AXIAL AND DIAGONAL BUX X 3025 W STAINLESS STEEL TUBES (SEE FIGS 4 AND T IN THE REPORT BODY), SERTIONAL AND MATERIAL PROPERTES OF THE TUBES ARE:

THE BUCKLING STRENGTH IS ESTIMATED BY THE ENERL FORMULA

$$\mathcal{L} = \frac{(\Gamma \backslash L)_{5}}{G \mu_{5} E}$$


FOR PINNED ENDS, C=1.0 AND THE MAXIMUM UNSUPPORTED LENGTH, L, is 76.43 in. THE BUCKUNG STESS 15  $G_{8} = \frac{(1.0)(\pi^{2})(28.5\times13)}{(76.43/127)^{2}} = 61/160 \text{ ps}$ 

Ty L JB L Ju

THUS THE YIELD STRESS LUIII BE CONSERVATIVELY USE FOR COMPUTING THE CRUSHING -OPS, IT IS

FT = UyA = (30,000 psi) (275 in2) = 32,50016

DISTRIBUTION OF LOADS IN THE INNESS FRAME CAN RE CLOSELY APPROXIMATED FROM THE RESULTS OF THE STATE PANALYEIS FOR 154016 LONGITUDINAL LONG APPLIED FIT ONE OF THE CURNERS, THE DISTRIBUTION FOR LINEAR ELASTIC BEHAVIOR IS APPROXIMATELY:



IN THE INNER FRAMME TRUSS MEMBERS

Pirc

TO PRODUCE FIRST YIELD THE APPLIED LUMB 15

 $= 1540 \times \frac{32500}{1030} = 123,350 \text{ lb}$ 

SUMMING THE LOAD FOR THE FOUR CORNERS GIVES A TOTAL CRUSH LOAD FOR THE INNER FRATILE OF

 $T_{IF} = 4 \times 123,35016 = 493,40016$ 

THE IS HIGHER THAN THE OUTER FRAME BUT LESS THAN THAT APPLIED TO IT BY THE FORKLY THEREFORE THE

(

TOTAL LONGITUDINAL CRUSHING LOND FOR THE CATIFACT
IN THE LONGITUDINAL DIRECTION IS, ASSUMING NO
POST BUCKLING LOND IN THE OUTER PRAME, THAT
DUE TO THE INNER PRAME AND SURROUNDING FORM
OR

$$F_{LC} = \frac{493,00015 + (1.25 \times 10^{2} - 391,000)15}{493,000 + 359,000}$$

$$= \frac{852,00015}{15}$$

THE CAMPACT SHOULD SUPPORT AT LETST THIS

MUCH LOAD, APPLIED UNIFORMLY THROUGH RIGID

PLATTENS, IN THE LONGITUDINAL DIRECTION. IT IS

VERY LIKELY THAT IT WILL REACT A HIGHER

LOAD BECAUSE OF STRAIN HARDENING IN THE

SOME FINITE

INNER PRAME TRUSS MEMBERS AND POST BUCKLING

LOAD CARRIED BY THE OUTER FRAME.

## YERTICAL LOADING

OF THE TWO DIRECTIONS, VERTICAL OR LATERAL, THE CAMPACT WILL HAVE A LOWER CRUSHING STREENGTH IN THE VERTICAL THAN IN THE LATERAL DIRECTION, THIS IS CAUSED PRIMARRILY BY THE FACT THAT THERE IS LESS FORM ON THE SIDES AND ENDS OF THE INNER FRAME TO RESIST THE VERTICAL LOADS.

BY HOPER LOADS IN THE DIAGONIZ MEMBERS.

TROM THE LONGITUDINAL ANALYSIS IT IS

CLEME THAT THE CRUSHING STRENGTH WILL BE
GOVERNOD BY THE CRUSHING STRENGTH OF THE
INNER TRAME AND FORTH. AN ADINA AMALYSIS

WAS DERFORMED TO ESTABLISH THE APPROXIMATE

DISTRIBUTION OF LOADS IN THE INNER FRAME

AND DOUR. RESULTS ARE SHOWN SCHEMATICALLY IN

FIGURE A-Z ON P. B. ASYMMETRY IN THE TRUSS

LOADS WERE CAUSED BY THE FORM ELEMIENTS (NOT

SHOWN) WHICH ARE ON THE LEFT-HAND SIDE,

TOP AND BOTTOM OF THE MODEL.

A CHECK OF RESULTS SHOWS THAT THE

DOUR REGION IS STRONGER & STIFFER THAN OTHER

REGIONS OF THE CAMPACT. NEVER-THE-LESS , FOR

CAMPACT
THESE ETTIMATES THE , CRUSH LOAD WILL BE

BASED ON RESULTS FOR THE LOADS APPLIED AT

"A AND B THE CRUSH LOAD FOR THE INDIVIDUAL

INTERNAL FRAME MEMBERS WILL BE THE SAME

AS COMPUTED FOIL LONGITUDINAL CRUSHING,

BELANSE THE YIELD LOAD GOVERNS FOR




FIGURE A-2. STATE LOADING OF THE INNER FRATIVE

THESE MEMBERS MISO. IT IS ( De pp. 4 = 5):

Fr = 92,50016

THE EXTERNAL LOAD, AT A and B OF

G

5.0

FIGURE A-2, to CAUSE CRUSHING OF THE CAMPACE 15 THEREFORE

$$=\frac{1000 \times \frac{92503}{626}}{626} = 131,79915$$

A LUAR OF THE MACNITUDE WILL BE RESISTED AT EIGHT POINTS ON THE INNER FRMIE; THUS THE CRUSH LUMD OF THE INDER FRAME IS

$$F_{IF} = 8 \times 131,78916$$
  
= 1.05 × 106 16

TO THIS CAN BE ADDED THE CRUSH STORISTA OF THE FORM SURROUNDING THE INNER FRAME, IT IS

$$A \approx 2 \times 7.31 \text{ m.} \times 233 + 31 \text{ m.} \times 89 \text{ m.} + 29'' \times 89 \text{ m.}$$

$$\approx 3406 + 2759 + 2842 = 9007 \text{ m.}^2$$

THE TOTAL CRUSH LOWP FOR THE CAMPACE IN THE VERTICAL DIRECTION IS THEN

$$\overline{V}_{c} = \overline{V}_{c} + \overline{V}_{c} = 1.05 \times 10^{6} + 1.26 \times 10^{6}$$

$$= 2.31 \times 10^{6} 15 >> F_{Lc}$$

THE MIN. CRUSHING LOAD FOR THE CAMPITE IS THEREFORE THAT FOR THE LONGITUDINAR DIRECTON AND IS

Fc = 852,0001b

APPENDIX B

CRUSHING STRENGTH OF THE CAMPACT - IMPACT OF THE CAMPACT WITH A RIGID SURFACE

# CRUSHING STRENGTH OF THE CAMPACT DURING

A SIMPLE CALCULATION IS USED TO OBTAIN AND EDUCATION CONSTRINT CRUSHNUL STRENGTH OF THE CAMPACT DURING IMPACT. THE KINETIC ENERGY AT IMPACT IS EQUATED TO THE DEFORMATION ELECTORY PROCESSED BY THE CAMPACT DURING THE TIMPACT EVENT OR

KE = F.D

WHERE

= \frac{1}{2} more energy AT IMPACT

D = MAXIMUM CRUSH OF THE CAMPACT COMPUTED IN THE ADINA ANALYSE

FOR DROPS, KE IS EQUAL TO THE INITIAL POTETITIAL ENERGY OR

KE=PE= mgh

FUR DROP HEIGHT N AND WEIGHT Mg.

### LATERAL DAMPACT

THE CAMPACT MASS REPRESENTED BY THE LATERAL MODEL WAS

$$mg = 22,583 \, lb + (3150 \, lb \, of FDAM)$$

$$= 25,733 \, lb$$

MINXIMUM CRUSH IN THE FORM WAS CALCULATED IN THE ADINA ANNUSIS AS:

WHICH GIVES AN EDUIVALENT CRUSHING STRENGTH OF THE CAMPACT FOR LATERAL IMPACT OF

$$\begin{aligned}
& + = \frac{KE}{D} = \frac{(25.733)(304 \times 12 \frac{10}{4})}{1.47} \\
& = \frac{6.30 \times 10^6}{15}
\end{aligned}$$

THIS FORCE IS ALMOST TWICE THE CRUSHING STRENGTH SF THE FORM WHICH IS:

$$\overline{L}_{50} = 100.36 \text{ m.} \times 229.44 \text{ in } \times 140 \text{ lb/ch}^2$$

$$= 3.22 \times 10^6 \text{ lb}$$

MAXIMUM TOTAL CRUSH OF THE CAMPACT BACK

FACE TO FRONT FACE) IS EQUAL TO THE CRUIH OF THE FORM PLUS THE FRAME
COMPRESSION, OR (SEE FIG. 3: IN THE REPORT
BODY)

D= 1.47 in. + 2.34 in. = 3,51 in.

FOR THE AMOUNT OF DEFORMATION THE CRUCH FORCE IS:

$$F = \frac{KE}{\Delta} = \frac{(25,733 \text{ lb.})(304 \times 12 \text{ m/H})}{3.81 \text{ lin}}$$

= 243 x10° 15

THEREFORE, THE ACTUAL CRUSH FORCE SHOULD BY:

2,43×10° 16 € FCRU € 6.30×10° 13